



Issued for Permit
08.05.2016

New Stanton, PA 15672

52 Blueberry Lane,
Grove City, PA 16127

No.	Issue Date	Project Status
-----	------------	----------------

As indicated

© 2016 JMAC Architects



2. STAIR FABRICATOR SHALL SUBMIT SHOP DRAWINGS WITH A PROFESSIONAL ENGINEER'S STAMP
3. STAIR FABRICATOR SHALL BE RESPONSIBLE FOR THE STAIR FABRICATION SYSTEM WITHIN THE STAIR TOWER OR STAIR AREA
3. THE GENERAL TRADES CONTRACTOR SHALL VERIFY ALL VERTICAL AND HORIZONTAL BUILDING DIMENSIONS AT ALL STAIR LOCATIONS WITH THE STAIR FABRICATOR
4. ALL MECHANICAL FASTENERS SHALL BE SUPPLIED BY THE FABRICATOR AND INSTALLED BY THE CONTRACTOR
5. DESIGN LOAD ON STAIRS 50 LBS PER SQ. FT. PLUS MATERIAL DEAD LOAD ON STAIRS 50 LBS PER LIN. FT. AND 200 LBS CONCENTRATED LOAD ON HANDRAILS AND GUARDRAILS.
6. SEE THE ROOM FINISH SCHEDULE FOR THE FLOOR AND LANDING FINISH: BASE, TREADS, RISERS, CEILING AND BULKHEADS FINISH